

25565-24

Northpoint Building Surveyors

APPROVED DOCUMENT

Works must comply with the

Building Act 1993 & Building Regulations

2018

24 HOURS NOTICE REQUIRED FOR INSPECTIONS

LOT 735 LEICHHARDT AVENUE, BURNSIDE HEIGHTS

STRUCTURAL DRAWINGS

SHEET LIST TABLE	
SHEET NUMBER	SHEET TITLE
S01	GENERAL NOTES
S02	GROUND FLOOR FOOTING & SLAB PLAN
S03	FOOTING & SLAB LEGEND
S04	FOOTING & SLAB DETAILS
S05	FOOTING & SLAB DETAILS
S06	FOOTING & SLAB DETAILS
S07	SITE DRAINAGE DETAILS
S08	SITE DRAINAGE DETAILS
S09	FIRST FLOOR FRAMING PLAN
S10	FIRST FLOOR FRAMING SCHEDULE
S11	ROOF FRAMING PLAN
S12	FRAMING DETAILS
S13	FRAMING DETAILS
S14	FRAMING DETAILS
S15	FRAMING DETAILS
S16	FRAMING DETAILS
S17	FRAMING DETAILS
S18	GROUND FLOOR WALL BRACING PLAN
S19	FIRST FLOOR WALL BRACING PLAN
S20	BRACING DETAILS
S21	BRACING DETAILS
S22	BRACING DETAILS
S23	BRACING DETAILS
S24	BRACING DETAILS
S25	TIE-DOWN SCHEDULE & DETAILS
S26	ARTICULATION JOINT PLAN

Client: AARON BOBADILLA

Revision: C1

Date: 03/12/25

GENERAL

G1 THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL OTHER CONSULTANTS DOCUMENTS, DRAWINGS & SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE CONTRACT AND PROJECT

G2 ALL DIMENSIONS AND CONDITIONS WHERE SHOWN ARE TO BE VERIFIED ON SITE. ENGINEERING DOCUMENTS ARE DIAGRAMMATIC AND MUST NOT BE SCALED. DISCREPANCIES IN ANY OF THE CONTRACT DOCUMENTS SHALL BE REFERRED TO THE DESIGN ENGINEER PRIOR TO PROCEEDING WITH THE WORK.

G3 MATERIALS & WORKMANSHIP ARE TO BE IN ACCORDANCE WITH THE RELEVANT CURRENT AUSTRALIAN STANDARDS & THE BUILDING CODE OF AUSTRALIA & ALL RELEVANT AUTHORITIES HAVING ANY JURISDICTION OVER ANY PART OF THE WORKS. G4 THESE NOTES ARE A SUPPLEMENT TO AND DO NOT REPLACE THE SPECIFICATIONS TO WHICH THE CONTRACTOR MUST CONFORM. SUBSTITUTION SHALL NOT BE PERMITTED WITHOUT THE APPROVAL OF THE ENGINEER.

G5 IT IS THE BUILDERS RESPONSIBILITY TO ENSURE THAT THE STRUCTURE & WORKS ARE MAINTAINED IN A STABLE CONDITION. NO PART SHALL BE OVER STRESSED DURING CONSTRUCTION.

G6 DESIGN LIVE LOADS:

ROOF:	0.25 KPa
FLOOR:	
- DWELLING	1.5 KPa
- GARAGE	2.5 KPa
BALCONY:	2.0 KPa

G7 INSPECTIONS: NO RESPONSIBILITY SHALL BE TAKEN UNLESS THE WORK IS INSPECTED AND APPROVED DURING CONSTRUCTION; ALL INSPECTION REQUIRED SHALL BE CONFIRMED 24 HOURS IN ADVANCE OF TIME REQUIRED

G8 HOME & INDUSTRIAL DOCUMENTS ARE NOT TO BE REPRODUCED IN FULL OR PART WITHOUT THE APPROVAL OF THIS OFFICE

G9 THE ARCHITECT IS TO REVIEW HOME & INDUSTRIAL CONSULTING ENGINEERS DOCUMENTS TO ENSURE CONSISTENCY WITH EXISTING CONDITIONS AND ANY RELEVANT CONSULTANT DOCUMENTS PRIOR TO ISSUE.

G10 NOT ALL SERVICES & DETAILS ARE IDENTIFIED ON THE DRAWINGS AND THE LOCATIONS ARE INDICATIVE ONLY. THE CONTRACTOR SHALL VERIFY THAT ALL REQUIREMENTS & EXISTING CONDITIONS AFFECTING THE WORKS ARE INCORPORATED INTO TENDER PRIOR TO COMMENCING THE WORK.

G11 WHERE WALLS ARE NOMINATED TO BE DEMOLISHED, CONTRACTOR TO VERIFY WITH DESIGN ENGINEER IF EXISTING CONDITION IS LOAD BEARING PRIOR TO COMMENCEMENT OF WORK.

CONCRETE

C1 CONCRETE CHARACTERISTIC COMPRESSION STRENGTH (F'c) TO BE 20 MPa MINIMUM AT 28 DAYS OR AS NOTED ON DRAWINGS. MAXIMUM SLUMP 100mm & 20MM NOMINAL AGGREGATE.

C2 CONCRETE FINISHES SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS OR ARCHITECTURAL DETAILS.

C3 CLEAR CONCRETE COVER TO NON PRE STRESSED REINFORCEMENT INCLUDING FITMENTS FOR CLASSIFICATIONS A & B1 SHALL BE AS FOLLOWS UNLESS OTHERWISE NOTED:

- FOR AREAS GREATER THAN 1km FROM COAST

ELEMENT	FORMED AND COVERED	FORMED AND EXPOSED
SLABS AND WALLS	20mm	30mm
BEAMS	25mm	40mm
COLUMNS	40mm	50mm
FOOTINGS	-	65mm

FOR AREAS OUTSIDE THE ABOVE REFER TO AS3600 FOR COVER REQUIREMENTS AND PRIOR TO STEEL SCHEDULING OR ORDERING CONTACT THIS OFFICE FOR CONFIRMATION OF COVERS

C4 CONCRETE COVERS SHALL BE MAINTAINED BY THE USE OF APPROVED CHAIRS AND SUPPORTS AT A MINIMUM OF 800MM CRS. CONDUITS, PIPES ETC. ARE NOT TO BE PLACED IN THE CONCRETE COVER. CONTRACTOR TO ENSURE CORRECT COVER CAN BE OBTAINED DURING REVIEW OF DOCUMENTS PRIOR TO TENDER SUBMISSION

C5 REINFORCEMENT MUST BE SECURELY FIXED IN POSITION TO PREVENT DISPLACEMENT WITH APPROVED SUPPORT METHODS AND SPACING

C6 CONCRETE SIZES SHOWN DO NOT INCLUDE FINISHES AND MUST NOT BE REDUCED. NO PENETRATIONS, CHASES, OR EMBEDMENTS OTHER THAN SHOWN ON THE STRUCTURAL DRAWINGS SHALL BE MADE WITHOUT WRITTEN APPROVAL FROM THE DESIGN ENGINEER.

C7 CONCRETE MEMBERS HAVE TO REACH A MINIMUM STRENGTH PRIOR TO CONSTRUCTION LOADING, CONTRACTOR TO CONFIRM WITH DESIGN ENGINEER REQUIRED STRENGTH

C8 DIAGONAL BARS 3-N12 BARS OR 3-L11TM x 2000 MM LONG SHALL BE PLACED ACROSS EACH INTERNAL CORNER (& OPENING) OF SLABS AND WALLS IN TOP SURFACE.

C9 REINFORCEMENT IS REPRESENTED DIAGRAMMATIC ALLY AND IS NOT NECESSARILY A TRUE PROJECTION. SPLICES ARE TO BE MADE ONLY IN LOCATIONS AS NOMINATED ON DRAWINGS UNLESS GIVEN WRITTEN APPROVAL FROM THE DESIGN ENGINEER. WELDING OF REINFORCEMENT IS NOT PERMITTED UNLESS NOMINATED ON DRAWINGS.

C10 CONSTRUCTION JOINTS WHERE NOT SHOWN ON DRAWINGS SHALL BE LOCATED TO THE APPROVAL OF THE DESIGN ENGINEER

C11 ALL CONCRETE SHALL BE CURED FOR A MINIMUM OF 7 DAYS AFTER CONCRETE POUR, UNLESS OTHERWISE NOTED IN DOCUMENTS.

C12 SAW CUT JOINTS WHERE SHOWN ON THE DRAWINGS SHALL BE MADE WITHIN 24 HOURS OF COMPLETION OF CONCRETE POUR.

C13 FORM WORK SHALL BE LEFT IN PLACE FOR THE MINIMUM TIME AS NOTED BELOW UNLESS OTHERWISE APPROVED IN WRITING FROM THE DESIGN ENGINEER.

- BEAM SIDES, VERTICAL WALLS AND COLUMNS 4 DAYS
- SLABS UP TO 4.5M SPANS (RE-PROPPING REQUIRED), 8 DAYS

- REMOVAL OF PROPS UNDER SLAB 28 DAYS
- BEAM SOFFITS UP TO 7.6M (PROPPING REQUIRED) 14DAYS

- REMOVAL OF PROPS UNDER BEAMS 24 DAYS

C14 ALL MATERIALS AND CONSTRUCTION IS TO BE IN ACCORDANCE WITH AS3600 AND AS1509

FOOTING, SLAB & GROUND NOTES

F1 ALL FOOTINGS ARE TO BE BASED ON NATURAL MATERIALS WITH A MINIMUM SAFE BEARING CAPACITY 150KPa FOR STRIP & PAD FOOTINGS,100KPa FOR SLAB BEAMS (U.N.O). THE DESIGN ENGINEER IS TO BE CONTACTED PRIOR TO POURING OF ANY CONCRETE TO VERIFY CONDITIONS. ALL GROUND WORKS, FOUNDATIONS AND BATTERS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE RECOMMENDATIONS OUTLINED IN THE GEOTECHNICAL REPORTS

F2 ALL FOUNDATIONS SLABS ETC. ARE TO BE INSPECTED BY THE RELEVANT AUTHORITY PRIOR TO CONCRETE POURING

F3 ALL GROUND WORKS, FOUNDATIONS AND BATTERS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE RECOMMENDATIONS OUTLINED IN THE AUSTRALIAN STANDARD AS2870. CONTRACTOR TO CARRY OUT THE RELEVANT INVESTIGATIONS PRIOR OR COMMENCEMENT OF WORKS TO ENSURE NOMINATED SLABS IS APPLICABLE U.N.O

F4 CONTRACTOR TO ENSURE THAT AREAS ADJACENT TO STRUCTURE ARE WELL GRADED & DRAINED TO PREVENT COLLECTION OF SURFACE WATER.

F5 DESIGN ENGINEER TO ADVISE ON THE SLAB THICKNESS WHERE HOT COILS ARE TO BE EMBEDDED INTO SLAB. WHERE NOT SPECIFIED ON ENGINEERS DOCUMENTS

F6 ALL JUNCTIONS, PIPES & CONNECTIONS ETC. OF DRAINAGE, SEWERAGE & SERVICE MATERIALS FOR THE PROJECT ARE TO INCORPORATE RELATIVE MOVEMENT OF THE STRUCTURE, SURFACE AND SUB-SURFACE CONDITIONS.

F7 WHERE FILL UNDER SLABS EXCEEDS 100MM IN DEPTH THE FILLING SHALL CONSIST OF :

(a) GRANULAR MATERIAL TO A DEPTH NOT GREATER THAN 600MM AND COMPACTED IN NOT GREATER THAN 150MM LAYERS.

(b) CLAY MATERIAL TO A DEPTH NOT GREATER THAN 300MM AND COMPACTED IN NOT GREATER THAN 150MM LAYERS. PROPOSED FILL MATERIAL DETAILS ARE TO BE SUBMITTED TO THE DESIGN ENGINEER FOR APPROVAL

F8 ALL DRAINAGE, SEWER & SERVICES AFFECTED BY FOUNDATION MOVEMENTS ARE TO BE FITTED WITH THE APPROPRIATE FLEXIBLE CONNECTIONS

F9 REINFORCEMENT LAPS TO BE AS FOLLOWS UNLESS OTHERWISE NOTED:

(a) N12 BARS, 500MM MINIMUM
(b) N16 BARS, 700MM MINIMUM
(c) TRENCH MESH SPlice NO LESS THAN 700MM
(d) TEE INTERSECTION & CORNERS TO BE FULL WIDTH
(e) SLAB REINFORCEMENT AS NOTED

F10 ALL EXCAVATIONS SHALL BE TAKEN OUT ACCURATELY TO THE LINES, LEVELS AND GRADES REQUIRED BY THE DOCUMENTS IN WHATEVER MATERIAL MAY BE ENCOUNTERED. (UNSUITABLE MATERIAL TO BE REMOVED & APPROVED BACKFILL REPLACED)

DISCLAIMER NOTE

THE CONSULTANT ACCEPTS NO RESPONSIBILITY OR LIABILITY FOR THE USE, APPROVAL, OR INSTALLATION OF NON-COMPLIANT OR NON-CONFORMING BUILDING PRODUCTS. THIS INCLUDES MATERIALS THAT DO NOT COMPLY WITH THE NATIONAL CONSTRUCTION CODE (NCC), RELEVANT AUSTRALIAN STANDARDS, OR APPLICABLE REGULATIONS.PROFESSIONAL INDEMNITY INSURANCE EXCLUDES COVER FOR ANY CLAIMS ARISING FROM SUCH PRODUCTS. IT IS THE RESPONSIBILITY OF THE BUILDER/SUPPLIER/INSTALLER TO ENSURE COMPLIANCE.

STRUCTURAL & STEEL WORKS

S1 ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH: AS1538, AS1539, AS1540, AS1541, AS1542, AS1543, AS1544, AS1545, AS1546, AS1547, AS1548, AS1549, AS1550, AS1551, AS1552, AS1553, AS1554, AS1555, AS1556, AS1557, AS1558, AS1559, AS1560, AS1561, AS1562, AS1563, AS1564, AS1565, AS1566, AS1567, AS1568, AS1569, AS1570, AS1571, AS1572, AS1573, AS1574, AS1575, AS1576, AS1577, AS1578, AS1579, AS1580, AS1581, AS1582, AS1583, AS1584, AS1585, AS1586, AS1587, AS1588, AS1589, AS1590, AS1591, AS1592, AS1593, AS1594, AS1595, AS1596, AS1597, AS1598, AS1599, AS1600, AS1601, AS1602, AS1603, AS1604, AS1605, AS1606, AS1607, AS1608, AS1609, AS1610, AS1611, AS1612, AS1613, AS1614, AS1615, AS1616, AS1617, AS1618, AS1619, AS1620, AS1621, AS1622, AS1623, AS1624, AS1625, AS1626, AS1627, AS1628, AS1629, AS1630, AS1631, AS1632, AS1633, AS1634, AS1635, AS1636, AS1637, AS1638, AS1639, AS1640, AS1641, AS1642, AS1643, AS1644, AS1645, AS1646, AS1647, AS1648, AS1649, AS1650, AS1651, AS1652, AS1653, AS1654, AS1655, AS1656, AS1657, AS1658, AS1659, AS1660, AS1661, AS1662, AS1663, AS1664, AS1665, AS1666, AS1667, AS1668, AS1669, AS1670, AS1671, AS1672, AS1673, AS1674, AS1675, AS1676, AS1677, AS1678, AS1679, AS1680, AS1681, AS1682, AS1683, AS1684, AS1685, AS1686, AS1687, AS1688, AS1689, AS1690, AS1691, AS1692, AS1693, AS1694, AS1695, AS1696, AS1697, AS1698, AS1699, AS1700, AS1701, AS1702, AS1703, AS1704, AS1705, AS1706, AS1707, AS1708, AS1709, AS1710, AS1711, AS1712, AS1713, AS1714, AS1715, AS1716, AS1717, AS1718, AS1719, AS1720, AS1721, AS1722, AS1723, AS1724, AS1725, AS1726, AS1727, AS1728, AS1729, AS1730, AS1731, AS1732, AS1733, AS1734, AS1735, AS1736, AS1737, AS1738, AS1739, AS1740, AS1741, AS1742, AS1743, AS1744, AS1745, AS1746, AS1747, AS1748, AS1749, AS1750, AS1751, AS1752, AS1753, AS1754, AS1755, AS1756, AS1757, AS1758, AS1759, AS1760, AS1761, AS1762, AS1763, AS1764, AS1765, AS1766, AS1767, AS1768, AS1769, AS1770, AS1771, AS1772, AS1773, AS1774, AS1775, AS1776, AS1777, AS1778, AS1779, AS1780, AS1781, AS1782, AS1783, AS1784, AS1785, AS1786, AS1787, AS1788, AS1789, AS1790, AS1791, AS1792, AS1793, AS1794, AS1795, AS1796, AS1797, AS1798, AS1799, AS1800, AS1801, AS1802, AS1803, AS1804, AS1805, AS1806, AS1807, AS1808, AS1809, AS1810, AS1811, AS1812, AS1813, AS1814, AS1815, AS1816, AS1817, AS1818, AS1819, AS1820, AS1821, AS1822, AS1823, AS1824, AS1825, AS1826, AS1827, AS1828, AS1829, AS1830, AS1831, AS1832, AS1833, AS1834, AS1835, AS1836, AS1837, AS1838, AS1839, AS1840, AS1841, AS1842, AS1843, AS1844, AS1845, AS1846, AS1847, AS1848, AS1849, AS1850, AS1851, AS1852, AS1853, AS1854, AS1855, AS1856, AS1857, AS1858, AS1859, AS1860, AS1861, AS1862, AS1863, AS1864, AS1865, AS1866, AS1867, AS1868, AS1869, AS1870, AS1871, AS1872, AS1873, AS1874, AS1875, AS1876, AS1877, AS1878, AS1879, AS1880, AS1881, AS1882, AS1883, AS1884, AS1885, AS1886, AS1887, AS1888, AS1889, AS1890, AS1891, AS1892, AS1893, AS1894, AS1895, AS1896, AS1897, AS1898, AS1899, AS1900, AS1901, AS1902, AS1903, AS1904, AS1905, AS1906, AS1907, AS1908, AS1909, AS1910, AS1911, AS1912, AS1913, AS1914, AS1915, AS1916, AS1917, AS1918, AS1919, AS1920, AS1921, AS1922, AS1923, AS1924, AS1925, AS1926, AS1927, AS1928, AS1929, AS1930, AS1931, AS1932, AS1933, AS1934, AS1935, AS1936, AS1937, AS1938, AS1939, AS1940, AS1941, AS1942, AS1943, AS1944, AS1945, AS1946, AS1947, AS1948, AS1949, AS1950, AS1951, AS1952, AS1953, AS1954, AS1955, AS1956, AS1957, AS1958, AS1959, AS1960, AS1961, AS1962, AS1963, AS1964, AS1965, AS1966, AS1967, AS1968, AS1969, AS1970, AS1971, AS1972, AS1973, AS1974, AS1975, AS1976, AS1977, AS1978, AS1979, AS1980, AS1981, AS1982, AS1983, AS1984, AS1985, AS1986, AS1987, AS1988, AS1989, AS1990, AS1991, AS1992, AS1993, AS1994, AS1995, AS1996, AS1997, AS1998, AS1999, AS2000, AS2001, AS2002, AS2003, AS2004, AS2005, AS2006, AS2007, AS2008, AS2009, AS2010, AS2011, AS2012, AS2013, AS2014, AS2015, AS2016, AS2017, AS2018, AS2019, AS2020, AS2021, AS2022, AS2023, AS2024, AS2025, AS2026, AS2027, AS2028, AS2029, AS2030, AS2031, AS2032, AS2033, AS2034, AS2035, AS2036, AS2037, AS2038, AS2039, AS2040, AS2041, AS2042, AS2043, AS2044, AS2045, AS2046, AS2047, AS2048, AS2049, AS2050, AS2051, AS2052, AS2053, AS2054, AS2055, AS2056, AS2057, AS2058, AS2059, AS2060, AS2061, AS2062, AS2063, AS2064, AS2065, AS2066, AS2067, AS2068, AS2069, AS2070, AS2071, AS2072, AS2073, AS2074, AS2075, AS2076, AS2077, AS2078, AS2079, AS2080, AS2081, AS2082, AS2083, AS2084, AS2085, AS2086, AS2087, AS2088, AS2089, AS2090, AS2091, AS2092, AS2093, AS2094, AS2095, AS2096, AS2097, AS2098, AS2099, AS2100, AS2101, AS2102, AS2103, AS2104, AS2105, AS2106, AS2107, AS2108, AS2109, AS2110, AS2111, AS2112, AS2113, AS2114, AS2115, AS2116, AS2117, AS2118, AS2119, AS2120, AS2121, AS2122, AS2123, AS2124, AS2125, AS2126, AS2127, AS2128, AS2129, AS2130, AS2131, AS2132, AS2133, AS2134, AS2135, AS2136, AS2137, AS2138, AS2139, AS2140, AS2141, AS2142, AS2143, AS2144, AS2145, AS2146, AS2147, AS2148, AS2149, AS2150, AS2151, AS2152, AS2153, AS2154, AS2155, AS2156, AS2157, AS2158, AS2159, AS2160, AS2161, AS2162, AS2163, AS2164, AS2165, AS2166, AS2167, AS2168, AS2169, AS2170, AS2171, AS2172, AS2173, AS2174, AS2175, AS2176, AS2177, AS2178, AS2179, AS2180, AS2181, AS2182, AS2183, AS2184, AS2185, AS2186, AS2187, AS2188, AS2189, AS2190, AS2191, AS2192, AS2193, AS2194, AS2195, AS2196, AS2197, AS2198, AS2199, AS2200, AS2201, AS2202, AS2203, AS2204, AS2205, AS2206, AS2207, AS2208, AS2209, AS2210, AS2211, AS2212, AS2213, AS2214, AS2215, AS2216, AS2217, AS2218, AS2219, AS2220, AS2221, AS2222, AS2223, AS2224, AS2225, AS2226, AS2227, AS2228, AS2229, AS2230, AS2231, AS2232, AS2233, AS2234, AS2235, AS2236, AS2237, AS2238, AS2239, AS2240, AS2241, AS2242, AS2243, AS2244, AS2245, AS2246, AS2247, AS2248, AS2249, AS2250, AS2251, AS2252, AS2253, AS2254, AS2255, AS2256, AS2257, AS2258, AS2259, AS2260, AS2261, AS2262, AS2263, AS2264, AS2265, AS2266, AS2267, AS2268, AS2269, AS2270, AS2271, AS2272, AS2273, AS2274, AS2275, AS2276, AS2277, AS2278, AS2279, AS2280, AS2281, AS2282, AS2283, AS2284, AS2285, AS2286, AS2287, AS2288, AS2289, AS2290, AS2291, AS2292, AS2293, AS2294, AS2295, AS2296, AS2297, AS2298, AS2299, AS2300, AS2301, AS2302, AS2303, AS2304, AS2305, AS2306, AS2307, AS2308, AS2309, AS2310, AS2311, AS2312, AS2313, AS2314, AS2315, AS2316, AS2317, AS2318, AS2319, AS2320, AS2321, AS2322, AS2323, AS2324, AS2325, AS2326, AS2327, AS2328, AS2329, AS2330, AS2331, AS2332, AS2333, AS2334, AS2335, AS2336, AS2337, AS2338, AS2339, AS2340, AS2341, AS2342, AS2343, AS2344, AS2345, AS2346, AS2347, AS2348, AS2349, AS2350, AS2351, AS2352, AS2353, AS2354, AS2355, AS2356, AS2357, AS2358, AS2359, AS2360, AS2361, AS2362, AS2363, AS2364, AS2365, AS2366, AS2367, AS2368, AS2369, AS2370, AS2371, AS2372, AS2373, AS2374, AS2375, AS2376, AS2377, AS2378, AS2379, AS2380, AS2381, AS2382, AS2383, AS2384, AS2385, AS2386, AS2387, AS2388, AS2389, AS2390, AS2391, AS2392, AS2393, AS2394, AS2395, AS2396, AS2397, AS2398, AS2399, AS2400, AS2401, AS2402, AS2403, AS2404, AS2405, AS2406, AS2407, AS2408, AS2409, AS2410, AS2411, AS2412, AS2413, AS2414, AS2415, AS2416, AS2417, AS2418, AS2419, AS2420, AS2421, AS2422, AS2423, AS2424, AS2425, AS2426, AS2427, AS2428, AS2429, AS2430, AS2431, AS2432, AS2433, AS2434, AS2435, AS2436, AS2437, AS2438, AS2439, AS2440, AS2441, AS2442, AS2443, AS2444, AS2445, AS2446, AS2447, AS2448, AS2449, AS2450, AS2451, AS2452, AS2453, AS2454, AS2455, AS2456, AS2457, AS2458, AS2459, AS2460, AS2461, AS2462, AS2463, AS2464, AS2465, AS2466, AS2467, AS2468, AS2469, AS2470, AS2471, AS2472, AS2473, AS2474, AS2475, AS2476, AS2477, AS2478, AS2479, AS2480, AS2481, AS2482, AS2483, AS2484, AS2485, AS2486, AS2487, AS2488, AS2489, AS2490, AS2491, AS2492, AS2493, AS2494, AS2495, AS2496, AS2497, AS2498, AS2499, AS2500, AS2501, AS2502, AS2503, AS2504, AS2505, AS2506, AS2507, AS2508, AS2509, AS2510, AS2511, AS2512, AS2513, AS2514, AS2515, AS2516, AS2517, AS2518, AS2519, AS2520, AS2521, AS2522, AS2523, AS2524, AS2525, AS2526, AS2527, AS2528, AS2529, AS2530, AS2531, AS2532, AS2533, AS2534, AS2535, AS2536, AS2537, AS2538, AS2539, AS2540, AS2541, AS2542, AS2543, AS2544, AS2545, AS2546, AS2547, AS2548, AS2549, AS2550, AS2551, AS2552, AS2553, AS2554, AS2555, AS2556, AS2557, AS2558, AS2559, AS2560, AS2561, AS2562, AS2563, AS2564, AS2565, AS2566, AS2567, AS2568, AS2569, AS2570, AS2571, AS2572, AS2573, AS2574, AS2575, AS2576, AS2577, AS2578, AS2579, AS2580, AS2581, AS2582, AS2583, AS2584, AS2585, AS2586, AS2587, AS2588, AS2589, AS2590, AS2591, AS2592, AS2593, AS2594, AS2595, AS2596, AS2597, AS2598, AS2599, AS2600, AS2601, AS2602, AS2603, AS2604, AS2605, AS2606, AS2607, AS2608, AS2609, AS2610, AS2611, AS2612, AS2613, AS2614, AS2615, AS2616, AS2617, AS2618, AS2619, AS2620, AS2621, AS2622, AS2623, AS2624, AS2625, AS2626, AS2627, AS2628, AS2629, AS2630, AS2631, AS2632, AS2633, AS2634, AS2635, AS2636, AS2637, AS2638, AS2639, AS2640, AS2641, AS2642, AS2643, AS2644, AS2645, AS2646, AS2647, AS2648, AS2649, AS2650, AS2651, AS2652, AS2653, AS2654, AS2655, AS2656, AS2657, AS2658, AS2659, AS2660, AS2661, AS2662, AS2663, AS2664, AS2665, AS2666, AS2667, AS2668, AS2669, AS2670, AS2671, AS2672, AS2673, AS2674, AS2675, AS2676, AS2677, AS2678, AS2679, AS2680, AS2681, AS2682, AS2683, AS2684, AS2685, AS2686, AS2687, AS2688, AS2689, AS2690, AS2691, AS2692, AS2693, AS2694, AS2695, AS2696, AS2697, AS2698, AS2699, AS2700, AS2701, AS2702, AS2703, AS2704, AS2705, AS2706, AS2707, AS2708, AS2709, AS2710, AS2711, AS2712, AS2713, AS2714, AS2715, AS2716, AS2717, AS2718, AS2719, AS2720, AS2721, AS2722, AS2723, AS2724, AS2725, AS2726, AS2727, AS2728, AS2729, AS2730, AS2731, AS2732, AS2733, AS2734, AS2735, AS2736, AS2737, AS2738, AS2739, AS2740, AS2741, AS2742, AS2743, AS2744, AS2745, AS2746, AS2747, AS2748, AS2749, AS2750, AS2751, AS2752, AS2753, AS2754, AS2755, AS2756, AS2757, AS2758, AS2759, AS2760, AS2761, AS2762, AS2763, AS2764, AS2765, AS2766, AS2767, AS2768, AS2769, AS2770, AS2771, AS2772, AS2773, AS2774, AS2775, AS2776, AS2777, AS2778, AS2779, AS2780, AS2781, AS2782, AS2783, AS2784, AS2785, AS2786, AS2787, AS2788, AS2789, AS2790, AS2791, AS2792, AS2793, AS2794, AS2795, AS2796, AS2797, AS2798, AS2799, AS2800, AS2801, AS2802, AS2803, AS2804, AS2805, AS2806, AS2807, AS2808, AS2809, AS2810, AS2811, AS2812, AS2813, AS2814, AS2815, AS2816, AS2817, AS2818, AS2819, AS2820, AS2821, AS2822, AS2823, AS2824, AS2825, AS2826, AS2827, AS2828, AS2829, AS2830, AS2831, AS2832, AS2833, AS2834, AS2835, AS2836, AS2837, AS2838, AS2839, AS2840, AS2841, AS2842, AS2843, AS2844, AS2845, AS2846, AS2847, AS2848, AS2849, AS2850, AS2851, AS2852, AS2853, AS2854, AS2855, AS2856, AS2857, AS2858, AS2859, AS2860, AS2861, AS2862, AS2863, AS2864, AS2865, AS2866, AS2867, AS2868, AS2869, AS2870, AS2871, AS2872, AS2873, AS2874, AS2875, AS2876, AS2877, AS2878, AS2879, AS2880, AS2881, AS2882, AS2883, AS2884, AS2885, AS2886, AS2887, AS2888, AS2889, AS2890, AS2891, AS2892, AS2893, AS2894, AS2895, AS2896, AS2897, AS2898, AS2899, AS2900, AS2901, AS2902, AS2903, AS2904, AS2905, AS2906, AS2907, AS2908, AS2909, AS2910, AS2911, AS2912, AS2913, AS2914, AS2915, AS2916, AS2917, AS2918, AS2919, AS2920, AS2921, AS2922, AS2923, AS2924, AS2925, AS2926, AS2927, AS2928, AS2929, AS2930, AS2931, AS2932, AS2933, AS2934, AS2935, AS29

EXISTING 100Ø SEWER TIE
DEPTH - 1.5m APPROX.
OFFSET - 3.5m APPROX.

FOOTING EXPOSURE:
NGL: RL 10.61
BOF: RL <9.84
O/S: 295mm

Northpoint Building Surveyors
APPROVED DOCUMENT
Works must comply with the
Building Act 1993 & Building Regulations
2018
24 HOURS NOTICE REQUIRED FOR INSPECTIONS

LOT 734 DOUBLE STOREY

LEICHHARDT LANE

EXISTING 225Ø SEWER PIPE
DEPTH - 4.0m APPROX.
OFFSET - 3.8m APPROX.

CONCRETE WIDENING
TO BE 100mm WIDER
THAN BRICK PIER
ABOVE. TYPICAL

DENOTES A 400mm WIDE EDGE BEAM WITH
4-L12TM BOTTOM & 3-L12TM TOP WITH
45mm SLIDING DOORS RECESS. REFER TO
DETAIL 'G.02'

ALL FFL MUST BE CONFIRMED WITH
APPROVED ARCHITECTURAL PLANS
BEFORE SLAB CONSTRUCTION (TYP.)

SHOWER RECESS, REFER TO
ARCHITECT. (IF REQUIRED).

NOTE -
REFER TO NEXT SHEET FOR FOOTING LEGEND


GROUND FLOOR SLAB PLAN

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision:
-	-	-		Drawn: Q.B		C1
-	-	-		Scale: 1:100 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25		Job no:		Sheet:
REVISION	COMMENT	DATE	Title: GROUND FLOOR FOOTING & SLAB PLAN	25565-24		S02 / 26

LEGEND




WHERE NOMINATED 3-L11TM OR 3-N12 BARS
(x2000 LONG) TIED TO UNDERSIDE OF SLAB MESH



HATCHED DENOTES EXTENT OF SLAB STEP
DOWN



DENOTES STARTING POINT FOR LAYOUT OF
WAFFLE POD BOXES



DENOTES BRICK WALL OVER



DENOTES WALL OVER



DENOTES INTERNAL LOAD BEARING WALL OVER

PAD3

DENOTES A 800x800 DEEP CONCRETE PAD TO BE
POSITIONED UNDER PORTAL COLUMN NOMINATED
WITH 50MM MIN. RECESS TO ACCOMMODATE
BASE PLATE. REFER TO DETAIL

PAD1

DENOTES A 600x600x600 MIN. DEEP CONCRETE
PAD TO BE FOUNDED MINIMUM 100mm INTO
STIFF NATURAL CLAY WITH 100kPa BEARING
CAPACITY

PAD2

DENOTES A 800x800x600 MIN. DEEP CONCRETE
PAD TO BE FOUNDED MINIMUM 100mm INTO
STIFF NATURAL CLAY WITH 100kPa BEARING
CAPACITY

BP1

450Ø CONCRETE DRILLED PIERS TO BE
FOUNDED 800mm INTO STIFF NATURAL CLAY
WITH 250kPa BEARING CAPACITY

BPT

450Ø CONCRETE DRILLED PIERS TO BE
FOUNDED A MINIMUM 2.5m DEEP OR DIRECTLY
ONTO NATURAL ROCK WITH 250kPa BEARING
CAPACITY

BP2

450Ø CONCRETE DRILLED PIERS TO BE FOUNDED
A MINIMUM DEPTH OF 1.40m AS WELL AS A
MINIMUM 800mm INTO STIFF NATURAL CLAY
WITH 250kPa BEARING CAPACITY

IF THE DEPTH OF THE DRILLED PIER IS NOT
ACHIEVED DUE TO ROCK/FLOATER ENCOUNTERED
AT SHALLOW DEPTH AND THAT CAN NOT BE
REMOVED WITH A SIZEABLE EXCAVATOR, 1200
LONG x 300 WIDE EXCAVATED PIER CAN BE
FOUNDED THROUGH FILL DIRECTLY ONTO
CONFIRMED CONTINUOUS ROCK/LARGE FLOATERS.

NOTE -
GROUND SURFACE BENCH TO SLOPE AWAY FROM
DWELLING 1 IN 20 FALL FOR 1.0m. WATER TO BE
COLLECTED BY STORM WATER SYSTEM.

SLAB DESIGN BASED ON FULL ARTICULATED MASONRY
VENEER AS PER AS2870 - 2011

NOTE:-
TREE SPECIES ON THE NATURE STRIP WAS NOT
AVAILABLE AT THE TIME OF DESIGN.
THEREFORE, FOR DESIGN PURPOSES, WE HAVE
ASSUMED A 15m MAX. MATURE HEIGHT TREE,
REQUIRING A PIERED SLAB DESIGN.
IF TREE SPECIES INFO CAN BE OBTAINED BY
THE BUILDER OR OTHERS, PIERS MAY BE
OMITTED IF THE TREE SPECIES IS FOUND TO
HAVE NO IMPACT ON THE SLAB DESIGN.
TREE INFO TO BE SENT TO THIS OFFICE PRIOR
TO CONSTRUCTION FOR FURTHER REVIEW.

CUT/FILL AND FFL'S REFERENCED AS PER
ARCHITECTURAL NO. : 042224
DATED: 20/01/2024
BUILDER MUST CONFIRM PRIOR TO CONSTRUCTION

GEOTECHNICAL REPORT UNDERTAKEN BY:
REF NO. : 25565-24 (DATED 05/06/2024)
COMPANY: H&I CONSULTING ENGINEERS
SITE CLASS: 'P' (AS 2870 - 2011)
THESE PLANS SHOULD BE READ IN CONJUNCTION WITH
GEOTECHNICAL REPORT

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision:
-	-	-		Drawn: Q.B	C1	
-	-	-		Scale: 1:100 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25		Job no:	25565-24	
REVISION	COMMENT	DATE	Title: FOOTING & SLAB LEGEND	S03 / 26		


WEEPHOLES HEIGHT TO ADJOINING GROUND LEVEL (75mm FOR PAVED, 150mm FOR NON PAVED AREA), REFER NCC FOR DETAILS.

FCL FALL 1 IN 20 FOR 1000MIN.

DEPTH (D)
150 MIN

REFER TO SCHEDULE FOR FOUNDING MATERIAL & DEPTH OF SLAB FOOTING.


F'C = 15MPa BLINDING CONCRETE WHERE REQUIRED WHEN BEAMS EXCEED 700mm IN DEPTH



TYPICAL EXTERNAL SLAB BEAM
SUSPENDED CROSS SECTION (125)

NOTES -

1. SLAB PLAN DIMENSIONS AND DETAILS (FLOOR STEP DOWNS, RECESSES ETC) MUST BE VERIFIED FROM ARCHITECTURAL DRAWINGS PRIOR TO CONSTRUCTION. ALL DIMENSIONS ARE IN MILLIMETERS.
2. SLAB ON GROUND DETAILS SHALL COMPLY WITH AS2870 - 2011
3. SITE PREPARATION - THE SLAB SUBGRADE SHALL BE SCRAPED CLEAR OF GRASS VEGETATION AND ORGANIC MATTER
4. THE GROUND WITHIN 1.5m OUTSIDE THE PERIMETER BEAM SHALL BE GRADED AWAY FROM THE BUILDING AT APPROXIMATELY 1: 20 SLOPE. REFER TO CLAUSE 5.6.3 AS2870 - 2011.
5. MOISTURE BARRIER SHALL BE 0.2mm POLYTHENE MATERIAL TAPED AT JOINTS LAPPING NOT LESS THAN 200mm. CARE MUST BE TAKEN DURING CONSTRUCTION TO PREVENT PUNCTURE OF MEMBRANE.



TYPICAL INTERNAL SLAB BEAM
SUSPENDED CROSS SECTION (125)

6. REINFORCEMENT - SLAB REINFORCEMENT FABRIC SHALL BE PLACED WITH A TOP COVER OF 25mm AND LAPPED THE 2 OUTERMOST TRANSVERSE WIRES MUST OVERLAP. BEAM REINFORCEMENT SHALL HAVE 65mm COVER TOP & BOTTOM, MINIMUM LAP OF 700mm. ALL REINFORCEMENT SHALL BE PLACED ON BAR CHAIRS AT A MAXIMUM SPACING OF 1200mm.
7. CONCRETE SHALL BE 20MPa GRADE, MAX. 100mm SLUMP U.N.O. CONCRETE SHALL BE CURED FOR AT LEAST 7 DAYS PRIOR TO PLACING OF BRICKWORK.
8. ALL RE-ENTRANT CORNERS SHALL HAVE 3-L11TM OR 3-N12 2000MM LONG PLACED AS SHOWN ON THE DRAWING. THESE MAY BE TIED TO THE UNDERSIDE OF THE SLAB MESH
9. PLUMBERS, PIPE EXCAVATIONS SHOULD BE KEPT AWAY FROM THE HOUSE. THE CLOSEST DISTANCE OF A TRENCH FROM SIDE OF A HOUSE IS IN GENERAL ITS DEPTH OF EXCAVATION. REFER TO CLAUSE 5.6.4 AS 2870 - 2011

Northpoint Building Surveyors
APPROVED DOCUMENT
Works must comply with the
Building Act 1995 & Building Regulations 2016
24 HOURS NOTICE REQUIRED FOR INSPECTIONS


SLAB SCHEDULE

SLAB THICKNESS	125mm
SLAB FABRIC	SL92 FABRIC CENTRAL
EXTERNAL BEAM SPECIFICATIONS	
DEPTH (D)	600mm MIN.
WIDTH (W)	300mm
BOTTOM REINFORCEMENT	3-L12TM
TOP REINFORCEMENT	3-L12TM
INTERNAL BEAM SPECIFICATIONS	
DEPTH (D)	600mm MIN.
WIDTH (W)	300mm
BOTTOM REINFORCEMENT	3-L12TM
TOP REINFORCEMENT	3-L12TM
BEAM FOUNDING DEPTH	A MINIMUM 100mm INTO STIFF NATURAL SILTY CLAY WITH A MINIMUM 100kPa BEARING CAPACITY OR DIRECTLY ONTO PIERS
CONCRETE STRENGTH = 20MPa AFTER 28 DAYS	
ALL SLAB COMPONENTS AS PER THIS TABLE U.N.O	


NOTES REGARDING DRAINAGE & TREES -

1. THIS SLAB HAS BEEN DESIGNED BASED ON A GOOD SITE DRAINAGE AS SHOWN IN TYPICAL DRAINAGE DETAILS
2. DESIGN FOR EXISTING TREES (IF REQUIRED) ARE SHOWN IN THIS DRAWING DOCUMENT ON THE BASIS OF INFORMATION SUPPLIED TO THIS OFFICE AT THE TIME OF DOCUMENTATION. THIS OFFICE SHOULD BE ADVISED IMMEDIATELY IF THERE IS DISCREPANCIES ON THE TREE INFORMATION.
3. UNLESS OTHERWISE DESIGNED FOR, TREES AND/OR LARGE SHRUBS SHOULD NOT BE ALLOWED TO GROW NEAR THE BUILDING WITHIN A DISTANCE EQUIVALENT TO THE MATURE HEIGHT OF THE TREE. THE DISTANCE SHOULD BE INCREASED BY 50% WHERE THERE ARE GROUPS OR ROWS OF TREES.
4. THE HOMEOWNER SHOULD BE AWARE OF THEIR RESPONSIBILITY TO MAINTAIN THE FOOTING SYSTEM AFTER OCCUPYING THE BUILDING. THIS IS CONTAINED IN THE CSIRO PUBLICATION "BTF-18-FOUNDATION MAINTENANCE AND FOOTING PERFORMANCE: A HOME OWNERS GUIDE". THIS COULD BE PURCHASED FROM: FREECALL 1300 788 000 OR ONLINE AT: <http://publish.csiro.au/pid/7076.htm>
5. IT IS THE BUILDER'S DIRECT RESPONSIBILITY TO ADVISE THE EXISTING OWNERS THAT THEY ARE RESPONSIBLE FOR AND UNDERSTAND THE IMPORTANCE OF FOLLOWING 1 TO 4 INCLUSIVE ABOVE AND THE POTENTIAL CONSEQUENCES OF NOT DOING SO. THE BUILDER MUST ALSO ENSURE THAT THE CURRENT OWNERS UNDERSTAND THE REQUIREMENT (AND POTENTIAL CONSEQUENCES) TO DO THE SAME WITH ANY SUBSEQUENT OWNERS (ALL COMMUNICATION MUST BE CONFIRMED IN WRITING).


-	-	-		Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-			Drawn: Q.B		
-	-	-			Scale: 1:20 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25			Job no:		Sheet:
REVISION	COMMENT	DATE			Title: FOOTING & SLAB DETAILS	25565-24	S04 / 26





TYPICAL STEPDOWN UPTO 344mm MAX.





DEEP EDGE REBATE DETAIL UPTO 1000mm
(WHERE REQUIRED)



TYPICAL SHOWER REBATE DETAIL
UPTO 50mm MAX.



-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision:
-	-	-		Drawn: Q.B		C1
-	-	-		Scale: 1:20 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25		Job no:		Sheet:
REVISION	COMMENT	DATE	Title: FOOTING & SLAB DETAILS	25565-24		S05 / 26




-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS Design: E.H Eng: J.P Drawn: Q.B Scale: 1:20 @ A3 Job no: 25565-24 Revision: C1
-	-	-	
-	-	-	
C1	CONSTRUCTION ISSUE	03/12/25	
REVISION	COMMENT	DATE	


Northcott Building Services
APPROVED DOCUMENT
AS PER AS 2870-2011 SECTION 5.6.3
Works must comply with the
Building Act 1993 & Building Regulations 2018
24 HOURS NOTICE REQUIRED FOR INSPECTIONS

DRAINAGE REQUIREMENTS
PREPARATION AND SHOULD BE COMPLETED BY END OF CONSTRUCTION

1. SURFACE DRAINAGE OF SITE TO BE CONTROLLED FROM START OF SITE PREPARATION AND SHOULD BE COMPLETED BY END OF CONSTRUCTION
2. TRENCH BASES TO SLOPE AWAY FROM BUILDING
3. TOP 300MM OF TRENCHES TO BE BACK-FILLED WITH MOIST COMPACTED CLAY WITHIN 1.5M FROM THE BUILDING
4. TRENCHES UNDER FOOTINGS TO BE PLUGGED WITH CLAY
5. SUBSOIL DRAINS NOT TO BE WITHIN 1.5M FROM BUILDING UNLESS DESIGNED IN ACCORDANCE WITH ENGINEERING PRINCIPLES



TYPICAL SITE DRAINAGE DETAIL
SCALE 1:50



**TYPICAL SEWER PENETRATION
TO EDGE BEAM DETAIL**

PLUMBING REQUIREMENTS

AS PER AS 2870 - 2011 SECTION 5.6.4




1. PENETRATION OF SERVICE PIPES AT EDGE BEAMS OR FOOTINGS TO BE AVOIDED WHERE PRACTICABLE. WHERE NECESSARY OR UNAVOIDABLE, SERVICE PIPE SHALL BE DETAILED TO ALLOW FOR MOVEMENT.
2. DRAINS EMERGING FROM UNDERNEATH THE BUILDING TO INCORPORATE FLEXIBLE JOINTS AND SHOULD ALLOW DIFFERENTIAL MOVEMENT IN ANY DIRECTION EQUAL TO THE ESTIMATED CHARACTERISTIC SURFACE MOVEMENT, Y_s .
3. ON SITE WASTE WATER TREATMENT UNITS TO BE LOCATED TO MINIMISE SOIL MOISTURE INCREASE WITHIN THE FOUNDATION.
4. DRAINAGE UNDER THE SLAB TO BE AVOIDED WHERE PRACTICABLE.
5. COLD AND HOT WATER PIPES NOT TO BE INSTALLED UNDER THE SLAB, UNLESS PIPES ARE INSTALLED WITHIN A CONDUIT SO THAT IF THE PIPE LEAKS IT WILL BE NOTICED ABOVE OR OUTSIDE THE SLAB

EXPANSION JOINT TABLE


Y_s	EXPANDA/ EXPANSION CAPACITY	SWIVEL JOINT	VERTICAL EXPANDA/ EXPANSION CAPACITY
>75	1 No. @ 150mm	2 No.	1No. @ 150mm
60 - 75	1 No. @ 100mm	2 No.	NOT REQUIRED
40 - 60	1 No. @ 60mm	1 No.	NOT REQUIRED
40	1 No. @ 60mm	1 No.	NOT REQUIRED

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-		Drawn: Q.B		
-	-	-		Scale: 1:20 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25			Job no:	Sheet:
REVISION	COMMENT	DATE		Title: SITE DRAINAGE DETAILS	25565-24	S07 / 26

Northpoint Building Surveyors
APPROVED DOCUMENT
Works must comply with the
Building Act 1993 & Building Regulations
2018
24 HOURS NOTICE REQUIRED FOR INSPECTIONS




**TYPICAL SERVICE PIPE WITHIN
1.5m OF EXTERNAL FOOTING**



TYPICAL PIPE PENETRATION THROUGH FOOTING

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-		Drawn: Q.B		
-	-	-		Scale: 1:20 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25		Job no:		Sheet:
REVISION	COMMENT	DATE	Title: SITE DRAINAGE DETAILS	25565-24	S08 / 26	



FIRST FLOOR FRAMING PLAN

IMPORTANT -
ALL FIRST FLOOR FRAMING MEMBERS HAVE BEEN DESIGNED FOR TRUSS ROOF CONSTRUCTION (WITHOUT THE TRUSS LAYOUT) . THE ROOF TRUSS LAYOUT AND COMPUTATIONS ARE TO BE PRESENTED TO THIS OFFICE BEFORE CONSTRUCTION TO VALIDATE THE FIRST FLOOR & ROOF FRAMING PLAN.

ALL TIMBER USED IN THIS PROJECT IS TO BE DRY AT TIME OF CONSTRUCTION

ALL EXPOSED TIMBER SHALL BE WATERPROOFED AND TREATED AS PER MANUFACTURERS SPECIFICATIONS

ALL EXPOSED STEEL TO BE HOT-DIP GALVANISED

NOTE -
ALL TIE DOWNS AND BRACING AS PER AS1684 - 2021

LOAD TRANSFER
POINT LOAD FROM SUPPORTING STUDS FROM UPPER FLOOR TO BE TRANSFERRED TO LOWER FLOOR SUPPORTS VIA COMPRESSION STUDS/BLOCKS.
LOWER STUDS TO BE SAME SIZE WITH STUDS ABOVE


- LEGEND**
- DENOTES WALL OVER
 - DENOTES WALL BELOW
 - DENOTES INTERNAL LOAD BEARING WALL UNDER
 - DENOTES BEAM SUPPORT / COLUMN POINT LOAD FROM ABOVE
 - DENOTES LOWER ROOF AREA
 - DENOTES BRICK WALL UNDER
 - DENOTES CONTINUOUS BEAM OVER SUPPORT
 - HATCHED DENOTES 50mm RECESS IF REQUIRED FOR SHOWER SETDOWN, FLOOR JOIST MANUFACTURER TO INCORPORATE INTO FLOOR JOISTS (TYP)

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision:
-	-	-		Drawn: Q.B	C1	
-	-	-		Scale: 1:100 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25		Job no:	Sheet:	
REVISION	COMMENT	DATE	Title: FIRST FLOOR FRAMING PLAN	25565-24	S09 / 26	

MEMBER SCHEDULE		
NAME	SECTION	REMARK
RL2	2-240x45 LVL13	NAIL LAMINATED
RL2+	150(V)x100(H)x10 UA	150 END SEAT
1B1	2-300x45 LVL13	NAIL LAMINATED. 2 SPAN CONTINUOUS
1B2	300x45 LVL13	
1B3	300x45 LVL13	
1B4	310 UC 137.0	PORTAL FRAME BEAM
1B5	310 UB 40.4	
1B6	2-300x45 LVL13	NAIL LAMINATED
1B7	2-300x45 LVL13	NAIL LAMINATED
1L1	200x10HOR + 250x12VERT INVERTED 'T'	250 END SEAT
1L2	200 PFC + 200x10 MS PLATE	
1L3	200 PFC + 200x10 MS PLATE	
1L4	200 PFC	
1L5	250 PFC + 200x10 MS PLATE	
1L6	200 PFC + 200x10 MS PLATE	
1L7	240x45 LVL13	NON LOAD BEARING LINTEL
1L8	2-240x45 LVL13	NAIL LAMINATED

MEMBER SCHEDULE		
NAME	SECTION	REMARK
1L8+	150(V)x100(H)x10 UA	150 END SEAT
1L9	2-240x45 LVL13	NAIL LAMINATED
1L9+	150(V)x100(H)x10 UA	150 END SEAT
PB1	200x45 LVL13	
ST1	150x100x6 RHS	WIND BEAM. REFER TO DETAIL
ST2	2-300x45 LVL13	NAIL LAMINATED. WIND BEAM. REFER TO DETAIL
1L	FIRST FLOOR LINTELS	REFER TO FRAMING SCHEDULE SHEET
FJ1	300 DEEP POSI-STRUTS OR EQUIVALENT	TO BE INSTALLED AS PER MANUFACTURERS SPECIFICATIONS
RT	ROOF TRUSSES	BY OTHERS
TS	3-90x45 MGP10	TIMBER STUDS
DC	2-90x45 F17 KDHW	TIMBER STUDS
P1	90x90 F7 TREATED PINE POST	H3 TREATED
HC1	89x89x5.0 SHS	HANGING COLUMN
C1	89x89x5.0 SHS	C350. STEEL COLUMN
C2(F)	89x89x6.0 SHS	C350. STEEL COLUMN. FULL HEIGHT TO TOP PLATE
C2	89x89x6.0 SHS	C350. STEEL COLUMN
C3	200x100x6.0 RHS	PORTAL FRAME COLUMN
B.G	BOX GUTTER	

-	-	-		Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-			Drawn: Q.B		
-	-	-			Scale: 1:100 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25				Job no:	Sheet:
REVISION	COMMENT	DATE		Title: FIRST FLOOR FRAMING SCHEDULE	25565-24		S10 / 26



ROOF FRAMING PLAN

IMPORTANT –
ROOF FRAMING DESIGNED WITHOUT THE TRUSS LAYOUT.
THE ROOF TRUSS LAYOUT AND COMPUTATIONS ARE TO
BE PRESENTED TO THIS OFFICE BEFORE CONSTRUCTION
TO VALIDATE THE FIRST FLOOR & ROOF FRAMING PLAN.

IMPORTANT –
ALL TIMBER USED IN THIS PROJECT IS TO BE DRY AT
TIME OF CONSTRUCTION

ALL EXPOSED TIMBER SHALL BE WATERPROOFED AND
TREATED AS PER MANUFACTURERS SPECIFICATIONS

LEGEND

— DENOTES WALL UNDER

NOTE –


ALL TIE DOWNS AND BRACING AS PER AS1684 – 2021

MEMBER SCHEDULE


NAME	SECTION	REMARK
RL1	2-190x45 MGP10	NAIL LAMINATED
RL	ROOF LINTELS	REFER TO FRAMING SCHEDULE
GT	GIRDER TRUSS	ASSUMED LOCATION TO BE CONFIRMED BY TRUSS MANUFACTURER
C2(F)	89x89x6.0 SHS	C350. STEEL COLUMN. FULL HEIGHT TO TOP PLATE
DS	2-90x45 MGP10	TIMBER STUDS
TS	3-90x45 MGP10	TIMBER STUDS

-	-	-		Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-			Drawn: Q.B		
-	-	-			Scale: 1:100 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25			Job no:	25565-24	Sheet: S11 /26
REVISION	COMMENT	DATE			Title: ROOF FRAMING PLAN		

NOTE -
200 END SEAT (U.N.O)




TYPICAL INVERTED 'T'
LINTEL DETAIL




TYPICAL ARTICULATION JOINT
BRICKWORK DETAIL

TIMBER STUD SCHEDULE								
ALL STUDS SHALL BE NAIL LAMINATED IN ACCORDANCE WITH AS1684.2		DS	DS1	TS	TS1	DC	TC	
		90x45	90x35	90x45	90x35	90x45	90x45	90x45
		MGP10	MGP10	MGP10	MGP10	F17 KDHW	F17 KDHW	F17 KDHW
LINTEL	NO. OF BEARING STUD	1	1	1	1	1	1	2
	NO. OF JAMB STUD	1	1	2	2	1	2	2
BEAM	NO. OF BEARING STUD	2	2	3	3	2	3	4



LINTEL SUPPORT ON STUDS



BEAM SUPPORT ON STUDS

ARTICULATION JOINT THICKNESS - SPACING TABLE			
SOIL CLASS	MASONRY WALL CONSTRUCTION & SURFACE FINISH	UP TO 4m HIGH FOR (AT) = 10mm	4m TO 8.5 HIGH FOR (AT) = 15mm
M, M-D	EXTERNAL FACE MASONRY	6.0	6.0
	EXTERNAL RENDERED &/OR PAINTED MASONRY	5.5	5.5
H1, H1-D	EXTERNAL FACE MASONRY	5.5	5.5
	EXTERNAL RENDERED &/OR PAINTED MASONRY	5.0	5.0
H2, H2-D	EXTERNAL FACE MASONRY	5.0	5.0
	EXTERNAL RENDERED &/OR PAINTED MASONRY	4.5	4.5
SIZES BASED AS4773.1 - 2010 MASONRY IN SMALL BUILDINGS. REFER TO TABLE 13.1			

LINTEL SCHEDULE - SUPPORTING SHEET ROOF ONLY (RL)		
SPAN	SIZE	COLUMN
960 MAX.	90x35 LVL HYSPAN	DS1
1260 MAX.	90x45 LVL HYSPAN	DS1
1560 MAX.	120x35 LVL HYSPAN	DS1
1860 MAX.	140x35 LVL HYSPAN	DS1
2160 MAX.	190x35 LVL HYSPAN	DS1
2460 MAX.	190x45 LVL HYSPAN	DS1
2760 MAX.	240x35 LVL HYSPAN	DS1
3060 MAX.	240x45 LVL HYSPAN	DS1
COLUMNS		
DS1 - 2-90x35 MGP10 STUDS		
NOTE - WHERE LINTEL DIRECTLY SUPPORTS GIRDER TRUSS RL LINTEL TO BE DOUBLED UP & EXTRA STUD EACH SIDE U.N.O.		
LINTELS DESIGNED FOR MAXIMUM RLW = 4.5M		

LINTEL SCHEDULE - SHEET ROOF SUPPORTING FIRST FLOOR (1L)		
SPAN	SIZE	COLUMN
960 MAX.	120x45 LVL HYSPAN	DS
1260 MAX.	140x45 LVL HYSPAN	DS
1560 MAX.	190x45 LVL HYSPAN	DS
1860 MAX.	190x45 LVL HYSPAN	DS
2160 MAX.	240x45 LVL HYSPAN	TS
2460 MAX.	2-240x45 LVL HYSPAN	DC
2760 MAX.	2-240x45 LVL HYSPAN	DC
3060 MAX.	2-290x45 LVL HYSPAN	TC
COLUMNS		
DS - 2-90x45 MGP10 STUDS		
TS - 3-90x45 MGP10 STUDS		
DC - 2-90x45 F17 KDHW		
TC - 3-90x45 F17 KDHW		
LINTELS DESIGNED FOR MAXIMUM RLW = 4.5M & FLW = 3.5M		

-	-	-		Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-			Drawn: Q.B		
-	-	-			Scale: 1:10 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25			Job no:	25565-24	Sheet: S12 /26
REVISION	COMMENT	DATE		Title: FRAMING DETAILS			


DOUBLE STOREY TIMBER FRAMING SCHEDULE				
LOWER FLOOR FRAMING				
LOCATION	MINIMUM SIZE	NOTES		
BOTTOM PLATE	35x90 MGP10	SUPPORTED ON CONCRETE SLAB		
TOP PLATE	2-90x45 MGP10	MAX. RLW = 7.5m, MAX. FLW = 3.6m		
WALL STUDS	MINIMUM SIZE	MAX. HEIGHT	MAXIMUM RLW & FLW	
	90x35 MGP10	3000	@450 CRS MAX. RLW = 6.0m, FLW = 3.5m	
NOTE - JAMB STUDS TO AS1684, LOWER FLOOR STUDS ARE NOT TO BE NOTCHED FOR BRACING				
UPPER FLOOR FRAMING				
LOCATION	MINIMUM SIZE	NOTES		
BOTTOM PLATE	90x45 MGP10	MAX. RLW = 4.8m		
	2-90x45 MGP10	MAX. RLW = 7.5m		
TOP PLATE	2-90x45 MGP10	MAX. RLW = 7.5m		
WALL STUDS	MINIMUM SIZE	MAX. HEIGHT	MAXIMUM RLW	
	90x35 MGP10	3000	@ 450 CRS - MAX. RLW = 7.5m	@600 CRS - MAX. RLW = 6.9m
	90x45 MGP10	3000	@ 450 CRS - MAX. RLW = 7.5m	@600 CRS - MAX. RLW = 7.5m
		3600	@ 450 CRS - MAX. RLW = 3.5m	-
	JAMB STUDS TO AS1684. MAXIMUM NOTCHING TO STUDS FOR UPPER FLOOR BRACING TO BE 20mm			
NOGGINGS	STUD NOGGINGS @ NO MORE THAN 1350 CRS			

Northpoint Building Surveyors

APPROVED DOCUMENT

Works must comply with the
Building Act 1993 & Building Regulations
2018

24 HOURS NOTICE REQUIRED FOR INSPECTIONS




TYPICAL POINT LOAD TRANSFER TO LOWER FLOOR DETAIL

BRICKWORK LINTEL SCHEDULE (U.N.O)									
BRICK HEIGHT (mm)	CLEAR SPAN OF OPENING (mm)								
	600	1000	1200	1500	1800	2100	2400	2700	3000
500	100x6 MS PLATE	75x100x6 UA	75x100x6 UA	75x100x6 UA	75x100x6 UA	75x100x6 UA	100x100x6 EA	100x100x8 EA	150x100x10 UA
1000	100x6 MS PLATE	75x100x6 UA	75x100x6 UA	75x100x6 UA	75x100x6 UA	100x100x8 EA	150x100x10 UA	150x100x10 UA	150x100x10 UA
1500	100x6 MS PLATE	75x100x6 UA	75x100x6 UA	75x100x6 UA	100x100x8 EA	150x100x10 UA	150x100x10 UA	150x100x10 UA	
2000	100x6 MS PLATE	75x100x6 UA	75x100x8 UA	100x100x8 EA	100x100x10 EA	150x100x10 UA	150x100x10 UA		
2500	100x6 MS PLATE	75x100x8 UA	75x100x8 UA	100x100x8 EA	100x100x10 EA	150x100x10 UA	150x100x10 UA		
3000		75x100x8 UA	75x100x10 UA	100x100x10 EA	150x100x10 UA	150x100x10 UA			
NOTE LINTELS TO HAVE MINIMUM 110 END SEAT (U.N.O) < 1000mm SPAN									
NOTE LINTELS TO HAVE MINIMUM 150 END SEAT (U.N.O) > 1000mm SPAN									
ALL BRICK LINTEL TO BE HOT DIP GALVANISED									


ALTERNATIVE TIMBER MEMBERS	
LVL HYSpan/LVL13	LVL15
140/150x45	140x42
190/200x45	190x42
240x45	240x42
290/300x45	290/300x42
360x45	360x42
360x63	360x58
400x45	400x42
400x63	400x58

-	-	-		Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-			Drawn: Q.B		
-	-	-			Scale: 1:10 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25				Job no:	Sheet:
REVISION	COMMENT	DATE		Title: FRAMING DETAILS	25565-24	S13 /26	




D = BOLT DIAMETER

**TYPICAL TIMBER BEAM/LINTEL
TO TIMBER POST
CONNECTION DETAIL**




**TYPICAL TIMBER BEAM/LINTEL
TO TIMBER POST
TOP VIEW**


TIMBER BEAM/LINTEL TO TIMBER POST CONNECTION SCHEDULE		
TIMBER BEAM	F17/LVL	MGP10
150 - 250 DEEP	2-M8 BOLTS	2-M8 BOLTS
251 - 360 DEEP	2-M10 BOLTS	2-M10 BOLTS
361 - 400 DEEP	2-M12 BOLTS	2-M12 BOLTS




**TYPICAL TIMBER POST TO
CONCRETE FOOTING/SLAB DETAIL**




**TYPICAL FLOOR JOISTS TO
STEEL 300 PFC**



**TYPICAL STEEL PFC
LINTEL & MS PLATE**




**TYPICAL STEEL BEAM TO
TIMBER COLUMN DETAIL**




-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision:
-	-	-		Drawn: Q.B		C1
-	-	-		Scale: 1:10 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25		Job no:		Sheet:
REVISION	COMMENT	DATE	Title: FRAMING DETAILS	25565-24		S14 / 26


Northpoint Building Surveyors
APPROVED DOCUMENT
Works must comply with the
Building Act 1993 & Building Regulations 2018
24 HOURS NOTICE REQUIRED FOR INSPECTIONS




**TYPICAL STEEL BEAM
TO STEEL COLUMN
CONNECTION**




**TYPICAL STEEL COLUMN TO
BASE PLATE DETAIL**




**TYPICAL STEEL COLUMN TO
BASE PLATE SLAB EDGE DETAIL
(WHERE REQUIRED)**




**TYPICAL STEEL COLUMN TO
CONCRETE CONNECTION**




**TYPICAL STEEL COLUMN TO
BASE PLATE CORNER DETAIL
(WHERE REQUIRED)**



TYPICAL TIMBER BEAM TO STEEL PFC




TYPICAL TIMBER BEAM TO STEEL UB/UC




**TYPICAL TIMBER
BEAM MINIMUM BOLT
SPACING DETAIL**


TIMBER BEAM TO STEEL BEAM CONNECTION SCHEDULE		
TIMBER BEAM	BOLT SIZE	PLATE SIZE
150 - 250 DEEP	2-M12 BOLTS	8mm MS
251 - 360 DEEP	3-M12 BOLTS	8mm MS
361 - 400 DEEP	3-M16 BOLTS	8mm MS



PLAN VIEW



**TYPICAL WIND BEAM (RHS) TO STEEL
COLUMN CONNECTION DETAIL**



TYPICAL TIMBER WIND BEAM DETAIL

-	-	-
-	-	-
-	-	-
C1	CONSTRUCTION ISSUE	03/12/25
REVISION	COMMENT	DATE

Project:
LOT 735 LEICHHARDT AVENUE
BURNSIDE HEIGHTS

Title:
FRAMING DETAILS

Design: E.H Eng: J.P
Drawn: Q.B
Scale: 1:10 @ A3


Job no:
25565-24

Revision:
C1


Sheet:
S15 / 26

10mm CAP PLATE
6 CFW AR


Northpoint Building Surveyors
10mm CAP PLATE
APPROVED DOCUMENT
6 CFW AR
Works must comply with the
Building Act 1993 & Building Regulations
2018
24 HOURS NOTICE REQUIRED FOR INSPECTIONS



TYPICAL STEEL PORTAL FRAME
DETAIL




STEEL PORTAL FRAME COLUMN (C3)
TO BASE PLATE DETAIL




STEEL PORTAL FRAME COLUMN (C3)
TO BASE PLATE DETAIL


-	-	-		Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-			Drawn: Q.B		
-	-	-			Scale: 1:10 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25			Job no:		Sheet:
REVISION	COMMENT	DATE			Title: FRAMING DETAILS	25565-24	S16 / 26



**TYPICAL TIMBER BEAM
TO TIMBER BEAM (AT VOID) DETAIL**



**TYPICAL TIMBER BEAM
TO TIMBER BEAM
(UP TO 240 DEEP BEAM U.N.O)**




**TYPICAL TIMBER BEAM
TO TIMBER BEAM
(OVER 240 DEEP BEAM U.N.O)**

**ALTERNATE TIMBER BEAM TO TIMBER
BEAM (AT VOID) CONNECTION -**
PROVIDE GANG-NAIL SPLITHANGER, TYPE SPH220
WITH 10 TYPE 14Gx30/65 LONG SCREWS TO SUITE,
EACH FACE
OR APPROVED EQUIVALENT, REFER MANUFACTURER'S
SPECIFICATIONS.


Northpoint Building Surveyors
APPROVED DOCUMENT
Works must comply with the
Building Act 1993 & Building Regulations
2018
24 HOURS NOTICE REQUIRED FOR INSPECTIONS

NOTE -
ALL CONNECTION DETAILS ARE SHOWN TO BE FLUSH
AT THE TOP AND ARE TYPICAL ONLY. LEVELS OF
ALL BEAMS ARE TO BE DETERMINED ON SITE BY
BUILDER. CHAMFERED ENDS MAY BE REQUIRED,
BUILDER TO DETERMINE. WHERE REQUIRED REFER TO
DETAILS OR CONTACT ENGINEERING DESIGN OFFICE.

TIMBER TO TIMBER CONNECTION SCHEDULE	
TIMBER BEAM	F17/LVL
120 - 150 DEEP	2-M10 BOLTS
151 - 240 DEEP	2-M12 BOLTS
201 - 240 DEEP	2-M12 BOLTS
241 - 300 DEEP	3-M12 BOLTS
301 - 360 DEEP	3-M12 BOLTS
360 - 500 DEEP	3-M16 BOLTS




**TYPICAL TIMBER BEAM
-MINIMUM BOLT SPACING DETAIL**



TIMBER TO TIMBER BEAM
B TO B
B TO B
B TO B

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-		Drawn: Q.B		
-	-	-		Scale: 1:10 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25			Job no:	Sheet:
REVISION	COMMENT	DATE	Title: FRAMING DETAILS	25565-24		S17 / 26



GROUND FLOOR WALL BRACING PLAN

NOTE -
WHERE ENGINEERED FLOOR JOISTS ARE USED, REFER TO MANUFACTURERS SPECIFICATIONS AND INSTALLATION GUIDES FOR CONNECTION OF UPPER FLOOR BRACING WALLS TO FLOORING SYSTEM.

BRACING DESIGN BASED ON 'N1' WIND RATING


TYPE OF BRACE → (B900) → LENGTH OF BRACE

(E) ■■■ DENOTES THE LOCATION OF TYPE E, 4.8mm
HARDBOARD BRACING TO BE INSTALLED AS
PER AS1684 - 2021 TABLE 8.18 (N).
REFER TO BRACING DETAILS FOR EXTRACT

(B) ■■■ DENOTES THE LOCATION OF TYPE B, 4.8mm
HARDBOARD BRACING TO BE INSTALLED AS
PER AS1684 - 2021 TABLE 8.18 (M). REFER TO
BRACING DETAILS FOR EXTRACT

(D) ■■■ DENOTES THE LOCATION OF BRACING
DIAGONAL CROSS METAL STRAP BRACE OR
SPEED BRACE TO BE INSTALLED AS PER
AS1684 - 2021 TABLE 8.18 (D). REFER TO
BRACING DETAILS FOR EXTRACT

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision:
-	-	-		Drawn: Q.B		C1
-	-	-		Scale: 1:100 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25		Job no:	25565-24	Sheet:
REVISION	COMMENT	DATE	Title: GROUND FLOOR WALL BRACING PLAN			S18 / 26



FIRST FLOOR WALL BRACING PLAN

NOTE -
REFER TO TIE-DOWN SCHEDULE ON SHEET S25 FOR
WALL FRAME TIE-DOWN CONNECTION EXCEPT WHERE
PLY BRACING IS USED

BRACING DESIGN BASED ON 'N1'
WIND RATING

TYPE OF BRACE (B900) LENGTH OF BRACE

(E) ■■■
(B) ■■■

DENOTES THE LOCATION OF TYPE E, 4.8mm
HARDBOARD BRACING TO BE INSTALLED AS
PER AS1684 - 2021 TABLE 8.18 (N). REFER TO
BRACING DETAILS FOR EXTRACT

DENOTES THE LOCATION OF TYPE B, 4.8mm
HARDBOARD BRACING TO BE INSTALLED AS
PER AS1684 - 2021 TABLE 8.18 (M). REFER TO
BRACING DETAILS FOR EXTRACT

(C) ■■■
(D) ■■■

DENOTES THE LOCATION OF DIAGONAL BRACING
ANGLE STRAP BRACE TO BE INSTALLED AS PER
AS1684 - 2021 TABLE 8.18 (C). REFER TO
BRACING DETAILS FOR EXTRACT. C2700 = 2400
- 2700 IN LENGTH.

DENOTES THE LOCATION OF BRACING
DIAGONAL CROSS METAL STRAP BRACE OR
SPEED BRACE TO BE INSTALLED AS PER
AS1684 - 2021 TABLE 8.18 (D). REFER TO
BRACING DETAILS FOR EXTRACT


-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-		Drawn: Q.B		
-	-	-		Scale: 1:100 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25		Job no:	25565-24	Sheet: S19 / 26
REVISION	COMMENT	DATE	Title: FIRST FLOOR WALL BRACING PLAN			

BRACED WALLS - BOTTOM PLATE TO TIMBER FLOOR CONNECTION


Northpoint Building Surveyors
APPROVED DOCUMENT
Works must comply with the
Building Act 1993 & Building Regulations
2018
24 HOURS NOTICE REQUIRED FOR INSPECTIONS

TABLE 1 - BRACED WALLS - BOTTOM WALL PLATE TO TIMBER FLOOR CONNECTION


BRACED WALLS
BOTTOM PLATES
PERPENDICULAR
TO FLOOR JOISTS
(UP TO 2.9KN/M
CAPACITY)



BRACED WALLS
BOTTOM PLATES
PARALLEL TO
FLOOR JOISTS
(UP TO 1.5KN/M
CAPACITY)
TYPE - C BRACE



BRACED WALLS
BOTTOM PLATES
PARALLEL TO
FLOOR JOISTS
(UP TO 2.9KN/M
CAPACITY)
TYPE - A,D & E
BRACE




NOTE: ABOVE CONNECTION RECOMMENDED ONLY FOR WALL BRACING PURPOSES.

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-		Drawn: Q.B		
-	-	-		Scale: 1:10 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25		Job no:		Sheet:
REVISION	COMMENT	DATE	Title: BRACING DETAILS	25565-24	S20 / 26	

BRACED WALLS - TOP PLATE TO FIRST FLOOR/ROOF TRUSSES

2-No.14 TYPE 17 BATTEN SCREWS x75mm LONG, EITHER END (TYPICAL) 'OR' NAILING PLATES 'OR' FRAMING ANCHORS (LEGS NOT BENT) TO EITHER END OF NOGGING/TRIMMER 6-2.8mmØ NAILS IN EACH FACE



REFER 'TABLE 2' FOR SPACING OF SHEAR BLOCKS TO BRACED WALL

PARALLEL BRACED WALL TO TRUSSES

8-2.8mmØ 'OR' 6-3.05mmØ NAILS WITH TIMBER SHEAR BLOCK ON BOTH SIDES

FLOOR JOISTS, TRUSSES & RAFTERS

BLOCKING PIECES LARGE ENOUGH TO AVOID SPLITTING


PERPENDICULAR BRACED WALL

GAP BETWEEN TOP PLATE TO FLOOR JOISTS, TRUSSES & RAFTERS WHERE REQUIRED

REFER 'TABLE 2' FOR SPACING OF SHEAR BLOCKS TO BRACED WALL

PERPENDICULAR BRACED WALL TO TRUSSES

Northpoint Building Surveyors
APPROVED DOCUMENT
Works must comply with the
Building Act 1993 & Building Regulations 2018
24 HOURS NOTICE REQUIRED FOR INSPECTIONS



REFER 'TABLE 2' FOR SPACING OF SHEAR BLOCKS TO BRACED WALL

PARALLEL BRACED WALL TO FLOOR JOISTS

TABLE 2

SPACING OF SHEAR BLOCK PAIRS
PERPENDICULAR / PARALLEL TO BRACED
SECTION OF WALL

BRACING TYPE	SPACING (mm)
A	1200
B/E	700
C	2700
D	1350

NOTE: MIN. 1 No PAIR OF SHEAR BLOCKS
REQUIRED FOR EACH BRACED WALL

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-		Drawn: Q.B		
-	-	-		Scale: 1:10 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25		Job no: 25565-24		Sheet: S21 / 26
REVISION	COMMENT	DATE	Title: BRACING DETAILS			


MINIMUM HARDBOARD THICKNESS 4.8mm	
FASTENER SPACING (mm)	
TOP & BOTTOM PLATES	40
VERTICAL EDGES & NOGGING	150
FIX BOTTOM PLATE TO FLOOR FRAME OR SLAB.	

PROVIDE 1-M10 COACH SCREW X 50mm LONG WITH 30X38mm WASHER TO EACH CORER OF BRACING (COACH SCREW & WASHER TO BE GALVANISED)

FIXING BOTTOM PLATE TO TIMBER FLOOR:
PLATES UP TO 38mm THICK
2-75x3.05mmØ NAILS TO EACH JOIST AT 450 MAX. CRS.
OR
PLATES 38mm TO 50mm THICK
WITH 2-90x3.05mmØ NAILS TO EACH JOIST AT 450 MAX. CRS.

X4

TYPE E - WALL BRACING



BRACING WALL - BOTTOM PLATE END FIXING TO SLAB TYPICAL DETAIL

DETAIL X4

TYPE E - HARDBOARD SHALL COMPLY WITH AS/NZS 1859.4. HARDBOARD SHALL BE NAILED TO FRAME USING MINIMUM 30X2.8mmØ GALZANISED FLAT-HEAD NAILS AND EQUIVALENT.

NAILS SHALL BE LOCATED A MINIMUM OF 10mm FOR THE VERTICAL EDGES AND 15mm FROM THE TOP AND BOTTOM EDGES.
MAXIMUM STUD SPACING = 600mm.
BRACING PANEL MINIMUM WIDTH = 460mm.


TYPE E - AS1684.2 - 2021 TABLE 8.18 (N)
EXTRACT
BRACING CAPACITY = 2.9kN/m

MINIMUM HARDBOARD THICKNESS 4.8mm	
FASTENER SPACING (mm)	
TOP & BOTTOM PLATES	40
VERTICAL EDGES & NOGGING	150
INTERMEDIATE STUDS	300

FIXING BOTTOM PLATE TO TIMBER FLOOR:
PLATES UP TO 38mm THICK
2-75x3.05mmØ NAILS TO EACH JOIST AT 450 MAX. CRS.
OR
PLATES 38mm TO 50mm THICK
WITH 2-90x3.05mmØ NAILS TO EACH JOIST AT 450 MAX. CRS.

X2

TYPE B - WALL BRACING



BRACING WALL - BOTTOM PLATE END FIXING TO SLAB TYPICAL DETAIL

DETAIL X2

- NOTES:
1. TYPE B - HARDBOARD SHALL COMPLY WITH AS/NZS 1859.4.
 2. HARDBOARD SHALL BE NAILED TO FRAME USING MINIMUM 30x2.8mmØ GALZANISED FLAT-HEAD NAILS OR EQUIVALENT.
 3. NAILS SHALL BE LOCATED A MINIMUM OF 10mm FOR THE VERTICAL EDGES AND 15mm FROM THE TOP AND BOTTOM EDGES. MAXIMUM STUD SPACING = 600mm.
 4. AT LEAST ONE SIDE OF THE BRACING WALL SHALL BE LINED WITH GYPSUM PLASTER BOARD OR EQUIVALENT.
 5. PROVIDE A 2mm EXPANSION GAP AROUND THE PERIMETER OF EVERY HARDBOARD PANEL.
 6. HORIZONTAL BUTT JOINTS ARE PERMITTED, PROVIDED FIXING TO NOGGING AT 40mm CENTRES.
 7. BRACING PANEL MINIMUM WIDTH = 900mm.

TYPE B - AS1684.2 - 2021 TABLE 8.18 (M)
EXTRACT

CONCRETE FLOOR BRACING CAPACITY = 5.0kN/m
TIMBER FLOOR BRACING CAPACITY = 2.9kN/m


-	-	-
-	-	-
-	-	-
C1	CONSTRUCTION ISSUE	03/12/25
REVISION	COMMENT	DATE

Northpoint Building Surveyors
APPROVED DOCUMENT
Works must comply with the
Building Act 1993 & Building Regulations
2018
24 HOURS NOTICE REQUIRED FOR INSPECTIONS

Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
	Drawn: Q.B		
	Scale: 1:10 @ A3		
Title: BRACING DETAILS	Job no: 25565-24	Sheet: S22 / 26	


NOTE 1.

- OPTION 1.** 1 No. PRYDA EZI STUD TIE SST
- OPTION 2.** 30x0.8mm GALV. METAL STRAP LOOPED OVER PLATE AND FIXED TO STUD WITH 3-30x2.8mmØ GALV. FLAT HEAD NAILS (OR EQUIVALENT) TO EACH END. ALTERNATIVELY, SINGLE STRAP TO BOTH SIDES WITH 3 NAILS PER STRAP END 'OR' EQUIVALENT ANCHORS OR OTHER FASTENERS.
- OPTION 3.** PRYDA STUD TIE ST3 'OR' ST4 'OR' STS3 'OR' PRYDA STRAP NAIL SN2C 'OR' SN2B ON BOTH SIDES OF THE FRAME.
- OPTION 4.** 1-MITEK STUDLOCK SL125 (FOR SINGLE TOP PLATE) 'OR' SL170 (FOR DOUBLE TOP PLATE), 'OR' EQUIVALENT FIXING METHODS, LOCATED CENTRAL TO TOP PLATE AND STUD, ADDITIONAL TO THE STANDARD NAILS.



BRACING WALL - BOTTOM PLATE END
FIXING TO SLAB TYPICAL DETAIL

DETAIL X3



TYPE C - WALL BRACING

NOTES:
TYPE C - TIMBER AND METAL ANGLE BRACES -
THE MAXIMUM DEPTH OF NOTCH OR SAW-CUT SHALL NOT EXCEED 20mm.
SAW-CUTS STUDS SHALL BE DESIGNED AS NOTCHED.

TYPE C - AS1684.2 - 2021 TABLE 8.18 (C)
EXTRACT
BRACING CAPACITY = 1.5kN/m

Northpoint Building Surveyors
APPROVED DOCUMENT
Works must comply with the
Building Act 1993 & Building Regulations
2018
24 HOURS NOTICE REQUIRED FOR INSPECTIONS

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-		Drawn: Q.B		
-	-	-		Scale: 1:10 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25		Job no:	25565-24	Sheet: S23 / 26
REVISION	COMMENT	DATE	Title: BRACING DETAILS			

NOTE 1A.

OPTION 1. 1 No. PRYDA EZI STUD TIE SST.


OPTION 2. 30X0.8MM GALV. METAL STRAP LOOPED OVER PLATE AND FIXED TO STUD WITH 4-30X2.8mmØ GALV. FLAT-HEAD NAILS (OR EQUIVALENT) TO EACH END.

ALTERNATIVELY PROVIDE SINGLE STRAPS TO BOTH SIDES, WITH 4 NAILS PER STRAP END OR EQUIVALENT ANCHORS OR OTHER FASTENERS.


OPTION 3. PRYDA STUD TIE ST3 'OR' STS3 'OR' PRYDA STRAP NAIL SN2 ON EACH WALL FACE.

OPTION 4. 1-MITEK STUDLOCK SL125 (FOR SINGLE TOP PLATE) 'OR' SL170 (FOR DOUBLE TOP PLATE), 'OR' EQUIVALENT FIXING METHODS, LOCATED CENTRAL TO TOP PLATE AND STUD, ADDITIONAL TO THE STANDARD NAILS.

30X0.8mm TENSIONED METAL STRAP
FIXED TO STUDS WITH ONE 30X2.8mmØ
GALV. FLAT-HEAD NAIL OR EQUIVALENT
AND TO PLATES WITH 4-30X2.8mmØ
GALV. FLAT-HEAD NAILS, OR
ALTERNATIVE METAL STRAP, FIXED AS
ABOVE, WITH A NET SECTIONAL AREA
NOT LESS THAN 21mm²



REFER
NOTE
1A.




NOTE:
ALTERNATIVELY SPEED
BRACING MAY BE USED IN
LIEU OF TENSIONED METAL
STRAPS FOR EXTERNAL
BRICK VENEER WALLS AND
INSTALLED AS PER ABOVE.

TYPE D - WALL BRACING

(D) - METAL STRAPS - TENSIONED - WITH STUD STRAPS

**BRACING WALL - BOTTOM PLATE END
FIXING TO SLAB TYPICAL DETAIL**

DETAIL



TYPE D - AS1684.2 - 2021 TABLE 8.18 (D)


EXTRACT

BRACING CAPACITY = 3.0kN/m

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS	Design: E.H	Eng: J.P	Revision: C1
-	-	-		Drawn: Q.B		
-	-	-		Scale: 1:10 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25				
REVISION	COMMENT	DATE	Title: BRACING DETAILS	25565-24		Sheet: S24 / 26


TIMBER ROOF LINTEL TIE DOWN SCHEDULE (SHEET ROOF) WIND CLASSIFICATION (NON-CYCLONIC AREAS): N1 & N2			
LINTEL SPAN		N1 & N2	
0 - 1200		G.I.S. x 1 TOP & BOTTOM 4-2.8ϕ NAILS EACH END + M10 BOLT TO SLAB OR G.I.S. TO TIMBER FLOOR FRAME	
1201 - 2400		G.I.S. x 1 TOP & BOTTOM 6-2.8ϕ NAILS EACH END + M10 BOLT TO SLAB OR G.I.S. TO TIMBER FLOOR FRAME	
2401 - 3000		G.I.S. x 2 TOP & BOTTOM 6-2.8ϕ NAILS EACH END + M10 BOLT TO SLAB WITH 10ϕ COACH SCREW OR G.I.S. TO TIMBER FLOOR FRAME	
FRAMING TIE DOWN SCHEDULE (SHEET ROOF) WIND CLASSIFICATION (NON-CYCLONIC AREAS): N1 & N2			
CONNECTION		N1	N2
SINGLE/ UPPER STOREY	STUDS TO BOTTOM/ TOP PLATES	G.I.S. @1200 MAX. CRS ALONG WALL WITH 4-30x2.8 NAILS TO EACH END OF STRAP	G.I.S. @ 1200 CRS LEG WITH 6-30x2.8ϕ NAILS EACH END OF STRAP
	BOTTOM PLATES TO SLAB	75 MASONRY NAILS, NAILED @ 1200 MAX. CRS	75 MASONRY NAILS, NAILED TO INTERNAL WALL BOTTOM PLATE @ 350 CRS OR 10ϕ MASONRY BOLTS @ 1200 CRS
			75 MASONRY NAILS, NAILED TO EXTERNAL WALL BOTTOM PLATE @ 450 CRS OR 10ϕ MASONRY BOLTS @ 1200 CRS
	BOTTOM PLATES TO FLOOR FRAME	2-75x3.05mm NAILS @ 600 CRS	2-75x3.05mm NAILS @ 600 CRS (G.I.S. FIRST FLOOR STUD TO GROUND FLOOR STUD WITH 10 NAILS EACH STUD, OR BUGLE SCREW 90 LONG @ 900 CRS TO JOIST OR BEAM)

- NOTES:
- EQUIVALENT FIXING IS PERMISSIBLE TO BE ADOPTED IN LIEU OF ABOVE SPECIFICATION AND IT MUST BE IN ACCORDANCE WITH AS1684.2-2021
 - REFER TO TRUSS MANUFACTURER FOR TIE-DOWN FIXING ON ROOF BATTENS AND RAFTERS/TRUSSES
 - HOUSE ASSUMED TO HAVE A MAXIMUM WIDTH OF 12m
 - STUDS ASSUMED TO BE AT 600 MAX. CRS.
 - THE TOP PLATE SHALL BE FIXED OR TIED TO THE LINTEL WITHIN 100mm OF EACH RAFTER/TRUSS, OR THE RAFTER/TRUSS FIXED DIRECTLY TO THE LINTEL WITH A FIXING OF EQUIVALENT TIE-DOWN STRENGTH TO THAT REQUIRED FOR THE RAFTER/TRUSS. SEE DETAIL
 - G.I.S. MEANS 30 x 0.8 GALVANISED IRON STRAP



TYPICAL TIMBER BEAM / LINTEL
TIE DOWN DETAIL

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS Title: TIE-DOWN SCHEDULE & DETAILS	Design: E.H Eng: J.P	Revision: C1
-	-	-		Drawn: Q.B	
-	-	-		Scale: 1:10 @ A3	
C1	CONSTRUCTION ISSUE	03/12/25		Job no: 25565-24	Sheet: S25 / 26
REVISION	COMMENT	DATE			



ARTICULATION JOINT PLAN

LEGEND

 DENOTES ADDITIONAL ARTICULATION JOINT IN BRICKWORK

-	-	-	Project: LOT 735 LEICHHARDT AVENUE BURNSIDE HEIGHTS Title: ARTICULATION JOINT PLAN	Design: E.H	Eng: J.P	Revision:
-	-	-		Drawn: Q.B		C1
-	-	-		Scale: 1:100 @ A3		
C1	CONSTRUCTION ISSUE	03/12/25		Job no:	25565-24	Sheet:
REVISION	COMMENT	DATE				S26 / 26